

Central Draw Project Phase 1:

1. Regional stormwater control at point of discharge from CD-P85
2. Regional Detention/Infiltration Basins CD-P85 and CD-P86 north and south
 - a. CD-P85/CD-P86 Connection
 - b. County Road #19 Stabilization
 - c. CD-P86 Berm
 - d. Military Road Crossing
 - e. 70th Street Stabilization

A berm will be constructed in the saddle between CD-P86 North and South Lobes in order to maximize storage in the North Lobe prior to discharging to the south. A master grading plan is established for CD-P86 South Lobe. A stabilized channel constructed from County Road 19 to Gables Lake to handle emergency flow is NOT planned. -Source *SWWD WMP 2007, Houston Engineering, Inc.*